

2017 Seward Road Culvert Extension

City of Fairfield Department of Public Works – Fairfield, Ohio – (513) 867-4200

- General Contractor – WG Stang
- Guardrail – Security Fence
- Construction Cost – \$177,158
- Engineering – Northwest Consultants, Inc.
- Construction Administration / Inspection – City of Fairfield

Project Description

This project was maintenance improvement project designed to replace a failing headwall. The culvert was extended in order to widen the shoulder and accommodate future roadway improvements. This project included extending the existing double barrel culvert which conveys the Miami-Erie Historic Canal.

Key Improvements

- New Concrete Headwall
- Extension of Twin 77”x 52” Conduit
- New Guardrail and End Treatments
- New Rapid Rectangular Flashing Beacons for the Bike Trail

This project was funded through local funds from the City of Fairfield’s Street Improvement Fund. This project was administered and inspected by the City’s Construction and Engineering Division.



After Construction:



August 24, 2017

RRFB Installation:



September 8, 2017

Project Timeline

- Designed in 2015
- Council Award - June 12, 2017
- Construction Begins - August 2017
- Final Completion - September 2017